

Single-Window Hub

and Virtuous Environmental



Government of India Ministry of Environment, Forest and Climate Change (Issued by the State Environment Impact Assessment Authority(SEIAA), Maharashtra)

To,

The Proprietor MILAN GALA

Dharti Nirman Builders & Developers, 641, Ijmima Complex, Raheja Metroplex, Off. Link Road, Behind GSC, Malad (W), Mumbai -400064

Subject: Grant of Environmental Clearance (EC) to the proposed Project Activity under the provision of EIA Notification 2006-regarding

Sir/Madam.

This is in reference to your application for Environmental Clearance (EC) in respect of project submitted to the SEIAA vide proposal number SIA/MH/MIS/262985/2022 dated 22 Mar 2022. The particulars of the environmental clearance granted to the project are as below.

1. EC Identification No.

2. File No.

3. **Project Type**

4. Category

5. Project/Activity including Schedule No.

6. Name of Project EC22B038MH110591

SIA/MH/MIS/262985/2022

New

B2

8(a) Building and Construction projects

Proposed Slum Rehabilitation Scheme at C.T.S. no 6A (pt) of village Malvani, C.T.S. no 3/A/1(pt) of village Charkop, Situated at Bhabarkar Nagar, Kandivali

west, Mumbai 400067.

Name of Company/Organization 7.

8. **Location of Project**

9 **TOR Date** **MILAN GALA**

Maharashtra

N/A

The project details along with terms and conditions are appended herewith from page no 2 onwards.

Date: 30/07/2022

(e-signed) Manisha Patankar Mhaiskar **Member Secretary** SEIAA - (Maharashtra)



Note: A valid environmental clearance shall be one that has EC identification number & E-Sign generated from PARIVESH.Please quote identification number in all future correspondence.

This is a computer generated cover page.

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

No. SIA/MH/MIS/262985/2022 **Environment & Climate** Change Department Room No. 217, 2nd Floor, Mantralaya, Mumbai-400032.

To M/s. Dharti Nirman Builders & Developers (Mr. Milan N. Gala), C.T.S. no 6A (pt) of village Malvani, C.T.S. no 3/A/1(pt) of village Charkop, Situated at Bhabarkar Nagar, Kandivali (W), Mumbai.

> : Environmental Clearance for proposed Slum Rehabilitation Scheme at Subject C.T.S. no 6A (pt) of village Malvani, C.T.S. no 3/A/1(pt) of village Charkop, Situated at Bhabarkar Nagar, Kandivali west, Mumbai by M/s. Dharti Nirman Builders & Developers (Mr. Milan N. Gala)

Reference: Application no. SIA/MH/MIS/262985/2022

This has reference to your communication on the above-mentioned subject. The proposal was considered by the SEAC-2 in its 132nd & 176th meeting under screening category 8 (a) B2 as per EIA Notification, 2006 and recommend to SEIAA. Proposal then considered in 199th & 246th (Day-1) meeting of State Level Environment Impact Assessment Authority (SEIAA).

Brief Information of the project submitted by you is as below:-

Sr. No.	Description	Details		
1	Proposal Number	SIA/MH/MIS/262985/2022		
2	Name of Project	Proposed Slum Rehabilitation Scheme at C.T.S. no 6A (pt) of village Malvani, C.T.S. no 3/A/1(pt) of village Charkop, Situated at Bhabarkar Nagar, Kandivali west, Mumbai 400067		
3	Project category	8(a) Building and Construction projects		
4	Type of Institution	Private		
5	Project Proponent	Name	M/s. Dharti Nirman Builders & Developers (Mr. Milan N. Gala)	
		Regd. Office address	641, Ijmima Complex, Raheja Metroplex, Off. Link road, Behind GSC, Malad (W), Mumbai – 400 064	

.			1	Contact nu	ımber	8286572999	
				e-mail		dhartibnd@gi	nail.com
6	Consultan	it .					
	COMBUNA			Enviro Policy Research India Pvt. Ltd. Certificate No – NABET/EIA/2124/IA0076			
					(Validity - 26.04.2024)		
	* .			Name: - Mr. Avick Sil			
		•		Contact Details – 9833825875,			
				avick1114@gmail.com, avick@eprindia.com			
7	Applied for	or		Fresh			
8		of the project		C.T.S. no	6A (pt) of vi	llage Malvani	, C.T.S. no
				3/A/1(pt) of village Charkop, Situated at			
	· ·			Bhabarkar	Nagar, Kan	divali west, M	ſumbai
				400067			
9	Latitude a	nd Longitude		19°12'16.9)"N 72°49'20	0.4"	
10	Plot Area	(sq.m.)		6181.60			
11	Deduction	ıs (sq.m.)		180.00			
12	Net Plot a	rea (sq.m.)		6001.60			
13	Ground co	overage (m ²) &%)	2313.50		Three Assessment	
				37.42%			
14	FSI Area	(sq.m.)		21,736.38			
15	Non-FSI ((sq.m.)		14,366.24			
16	Proposed	built-up area (FS	I + Non	36,102.62			F F Fit
1 4 h	FSI) (sq.n	n.)					
				1888 Sec			
17	17 a * 1628) approved by F	lanning	21,736.38			
[Authority	till date					
18	1 100	EC details with	**************************************	NA		i (^{gra} nain A.	tel :
	Construct	ion area, if any.					
				NTA	LARSHWY Y T	<u>a 4. V</u>	
19		ion completed	1 37 37 2	NA		%	
	earlier EC	C (FSI + Non FSI)	(sq.m.)				
20	Previous EC / Existing Building		Dwar	osed Config	uration	Reason for	
20	Buildin	···		Buildin	Configura		Modificatio
		Configuratio	Heigh t		Configura	tilo rieigii	n / Change
	g Name	n	(m)	Name	11	(m)	II. Cimigo
	Taine	NA NA	(111)	Rehab	G + 22nd	67	_
		INV		ixilab	floors	07	
				Sale	Ground (pt	t) + 68.95	
	1			Dale	Cround (b)	9 00.93	<u> </u>

+ 4 Balwadi + 3			
le Building: 234			
ss Centre + 12			
Shops			
Sale Building: 234 Flats + 15 Shops			
2705			
322 KLD			
Ground Floor			
MCGM			
MBBR			
Ground Floor			
LD			
ewer line – 45.3 %			
ty (Kg/d) Treatmen			
t /.			
disposal			
Handover			
to			
authorized			
recycler			
OWC			
7 A			
ty (Kg/d) Treatmen			
t/			
disposal			
/Day Handover			
to			
authorized			
recycler			
/Day OWC			
-			
Would be			
used as			
manure			

R.G. Area in sq. m. RG required - 480.13 Sq.mt RG provided on Mother earth- 482.67 Sq.mt RG provided on ground - 482.67 Sq.mt Total - 482.67 Sq.mt Existing trees on plot: 30 (27 nos of trees have been planted on site and 3 nos of trees to be cut: 00 Number of trees to be transplanted: 00 During Operation Phase: Details Connected load (kW) 1480 33				
RG provided on ground - 482.67 Sq.mt Total - 482.67 Sq.mt Existing trees on plot: 30 (27 nos of trees have been planted on site and 3 nos of trees are existing on plot) Number of trees to be cut: 00 Number of trees to be transplanted: 00 During Operation Phase: Details Connected load (kW) Demand load (kW) 1480 33	31	R.G. Area in sq. m.	RG required – 480.13 Sq.mt	
Total — 482.67 Sq.mt Existing trees on plot: 30 (27 nos of trees have been planted on site and 3 nos of trees are existing on plot) Number of trees to be cut: 00 Number of trees to be transplanted: 00 During Operation Phase: Details Connected load (kW) Demand load (kW) 1480 33			RG provided on Mother earth- 482.67 Sq.mt	
Existing trees on plot: 30 (27 nos of trees have been planted on site and 3 nos of trees to be cut: 00 Number of trees to be transplanted: 00 32 Power requirement During Operation Phase: Details Connected load (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No, of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits 37 Project Cost in (Cr.) 38 EMP Cost Construction phase – 5 Lacs Operation phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	,		RG provided on ground - 482.67 Sq.mt	
(27 nos of trees have been planted on site and 3 nos of trees are existing on plot) Number of trees to be cut: 00 Number of trees to be transplanted: 00 32 Power requirement During Operation Phase: Details Connected load (kW) Demand load			Total – 482.67 Sq.mt	
nos of trees are existing on plot) Number of trees to be cut: 00 Number of trees to be transplanted: 00 32 Power requirement During Operation Phase: Details Connected load (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers - 127 nos 2 wheelers - 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 146 Cr 38 EMP Cost Construction phase - 5 Lacs Operation phase - 126 Lacs, OM cost - 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.rt the project and project			Existing trees on plot: 30	
Number of trees to be cut: 00 Number of trees to be transplanted: 00 32 Power requirement During Operation Phase: Details Connected load (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 127 nos 2 wheelers – 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 38 EMP Cost Construction phase – 5 Lacs Operation phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project			_ ·	
Number of trees to be transplanted: 00 During Operation Phase: Details Connected load 4168 (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers - 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 146 Cr Construction phase - 5 Lacs Operation phase - 126 Lacs, OM cost - 26.6 lacs. 39 CER Details with justification if anyas per MoEF & CC circular dated 01/05/2018 40 Details of Court Cases/litigations No w.r.t the project and project No				
During Operation Phase: Details			- 原生の17日間の原理の17日時間の19日間の19日間の19日間の19日間の19日間の19日間の19日間の19日	
Details Connected load (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 127 nos 2 wheelers – 60 nos RWH Capacity 37 CMD Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project			Number of trees to be transplanted: 00	
Connected load (kW) Demand load (kW) 1480 33 Energy Efficiency a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits; 8 Nos. 37 Project Cost in (Cr.) 146 Cr 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	32	Power requirement		
Construction phase - 126 Lacs, OM cost - 26.6 lacs. Construction phase - 126 Lacs, OM cost - 26.6			7 M OHING REPORT 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
Demand load (kW) 1480				
a) Total Energy saving (%): 13% b) Solar energy (%): 4.8% 34 D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 36 No. & capacity of Rain water harvesting tanks /Pits 37 Project Cost in (Cr.) 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project			10 10 12 13 14 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
b) Solar energy (%): 4.8% D.G. set capacity DG set as Power back-up during operation phase: Alternate Source Meter No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. Project Cost in (Cr.) EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 Details of Court Cases/litigations w.r.t the project and project			The section of the section of Section Section 180 on the Section 180 of the Section 180 o	
DG set as Power back-up during operation phase: Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits; 8 Nos. 37 Project Cost in (Cr.) 146 Cr 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	33	Energy Efficiency		
Alternate Source Meter 35 No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos 8 RWH Capacity 37 CMD Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 146 Cr 2 Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 1.09 Cr 40 Details of Court Cases/litigations w.r.t the project and project No			- Street Control Contr	
No. of 4-W & 2-W Parking with 25% EV 2 wheelers – 60 nos 2 wheelers – 60 nos 36 No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 146 Cr 2 Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 1.09 Cr 2 Construction phase – 126 Lacs, OM cost – 26.6 lacs. 1.09 Cr 2 Construct	34	D.G. set capacity	MENTERS 10 10 10 10 10 10 10 1	
25% EV 2 wheelers – 60 nos No. & capacity of Rain water harvesting tanks /Pits Recharge pits: 8 Nos. Project Cost in (Cr.) 146 Cr REMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. CER Details with justification if any as per MoEF &CC circular dated 01/05/2018 Details of Court Cases/litigations w.r.t the project and project			## 1 C C C C C C C C C C	
No. & capacity of Rain water RWH Capacity 37 CMD Recharge pits: 8 Nos.	35			
harvesting tanks /Pits Recharge pits: 8 Nos. 37 Project Cost in (Cr.) 146 Cr 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project		■ 100 1 895 350 3 30 30 30 30 30 30 30 30 30 30 30 30	大大 17 1 1 1 1 1 1 1 1	
37 Project Cost in (Cr.) 38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	36			
38 EMP Cost Construction phase – 5 Lacs Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project			The contract of the contract o	
Operation phase – 126 Lacs, OM cost – 26.6 lacs. 39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	-	. 9-9 * AMBO	Your	
39 CER Details with justification if anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	38	EMP Cost	1	
anyas per MoEF &CC circular dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project				
dated 01/05/2018 40 Details of Court Cases/litigations w.r.t the project and project	39	 1 25 (2) (40 (40 (40 (40 (40 (40 (40 (40 (40 (40	1.09 Cr	
40 Details of Court Cases/litigations No w.r.t the project and project		1 Total Children Dalawar Control September 1		
w.r.t the project and project			The second secon	
	40		No	
location, if any				
		location, if any.		

3. Proposal is a violation of EIA Notification, 2006. PP applied under violation amnesty OM dated 14.03.2018 on ecmpcb portal within the amnesty period. Proposal has been considered by SEIAA in its 199th & 246th (Day-1) meeting and decided to accord Environment Clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implantation of following terms and conditions-

Specific Conditions:

A. SEAC Conditions-

- 1. PP to ensure that STP to be kept open minimum up to 40%.
- 2. The discharge of treated sewage to be reduced to 35% as proposed during presentation.
- 3. PP to adopt water conservation measures by providing Low Flow Devices (LFD) as plumbing fixtures.
- 4. PP to ensure that the energy savings from renewable sources shall be minimum 5%.

- 5. PP to provide fire hydrant system along with all necessary Equipment's along with ladder for fireman at podium.
- 6. The RG 1 & 2 area shown in the plan is is less than 125Sq. meter hence it does not qualify as RG. PP to revisit the plan and provide RG area on ground as per Norms.
- 7. PP to include Environmental Monitoring plan in the Environmental management plan & implement the same.
- 8. PP to abide all conditions of NOCs granted by the different authorities.
- 9. The PP to get NOC from competent authority with reference to Thane creek flamingo sanctuary if the project site falls within 10 Km radius from the said sanctuary boundary, if applicable. The planning authority to ensure fulfilment of this condition before granting CCS
- 10. PP to submit CER prescribed by MoEF&CC circular dated 1.5.2018 relevant to the area and people around the project. The specific activities to be undertaken under CER to be carried out in consultation with Municipal Corporation or collector or Environment Department.

B. SEIAA Conditions-

- 1. PP has submitted a bank guarantee of Rs.2.46 lakhs (Rs.2.46 Crores) to Maharashtra Pollution Control Board towards effective implementation of the EMP comprising remediation plan and Natural and Community Resource augmentation Plan. PP to complete implementation of the EMP comprising remediation plan and Natural and Community Resource augmentation Plan within 1 year of grant of Environment Clearance.
- 2. PP to submit CER as applicable as per MOEF & CC circular dated 1.5.2018 in consultation with Municipal Corporation.
- 3. PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
- 4. SEIAA decided to decided to grant EC for FSI: 21736.38 m2, Non-FSI: 14366.24 m2 and Total BUA: 31102.62 m2 (Plan Approval no-Rehab Building: Occupation Certificate: SRA/ENG/2497/RS/STGL/AP dated 16.04.2018 Sale Building: IOA Letter: SRA/ENG/3092/RS/STGL/AP dated: 01.12.2018)

General Conditions:

a) Construction Phase :-

- I. The solid waste generated should be properly collected and segregated. Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. Disposal of muck, Construction spoils, including bituminous material during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in the approved sites with the approval of competent authority.
- III. Any hazardous waste generated during construction phase should be disposed of as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- IV. Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be

ensured.

- V. Arrangement shall be made that waste water and storm water do not get mixed.
- VI. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices.
- VII. The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- VIII. Permission to draw ground water for construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
 - IX. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
 - X. The Energy Conservation Building code shall be strictly adhered to.
 - XI. All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- XII. Additional soil for levelling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- XIII. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- XIV. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas)
 Protection and Preservation of Trees Act, 1975 as amended during the validity of
 Environment Clearance.
- XV. The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- XVI. PP to strictly adhere to all the conditions mentioned in Maharashtra (Urban Areas)
 Protection and Preservation of Trees Act, 1975 as amended during the validity of
 Environment Clearance.
- XVII. Vehicles hired for transportation of Raw material shall strictly comply the emission norms prescribed by Ministry of Road Transport & Highways Department. The vehicle shall be adequately covered to avoid spillage/leakages.
- XVIII. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
 - XIX. Diesel power generating sets proposed as source of backup power for elevators and common area illumination during construction phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel is preferred. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
 - XX. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings by a separate environment cell /designated person.

B) Operation phase:-

- I. a) The solid waste generated should be properly collected and segregated. b) Wet waste should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. c) Dry/inert solid waste should be disposed of to the approved sites for land filling after recovering recyclable material.
- II. E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
- III. a) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/ reused to the maximum extent possible. Treatment of 100% grey water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP. b) PP to give 100 % treatment to sewage /Liquid waste and explore the possibility to recycle at least 50 % of water, Local authority should ensure this.
- IV. Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement.
- V. The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
- VI. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- VII. PP to provide adequate electric charging points for electric vehicles (EVs).
- VIII. Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/Agriculture Dept.
- IX. A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- X. Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes.
- XI. The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at parivesh.nic.in
- XII. Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.

- XIII. A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
- XIV. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.

C) General EC Conditions:-

- I. PP has to strictly abide by the conditions stipulated by SEAC& SEIAA.
- II. If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- III. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- IV. The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
- V. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
- VI. No further Expansion or modifications, other than mentioned in the EIA Notification, 2006 and its amendments, shall be carried out without prior approval of the SEIAA. In case of deviations or alterations in the project proposal from those submitted to SEIAA for clearance, a fresh reference shall be made to the SEIAA as applicable to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
- VII. This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
- 4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP

Act.

- 5. This Environment Clearance is issued purely from an environment point of view without prejudice to any court cases and all other applicable permissions/ NOCs shall be obtained before starting proposed work at site.
- 6. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
- 7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, amended from time to time.
- 8. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
- 9. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1st Floor, D-Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Manisha Patanga Mhajekar 22 (Member Secretary, SEIAA)

Copy to:

- 1. Chairman, SEIAA, Mumbai.
- 2. Secretary, MoEF & CC, IA- Division MOEF & CC
- 3. Member Secretary, Maharashtra Pollution Control Board, Mumbai.
- 4. Regional Office MoEF & CC, Nagpur
- 5. District Collector, Mumbai Suburban.
- 6. Commissioner, Municipal Corporation of Greater Mumbai
- 7. Regional Officer, Maharashtra Pollution Control Board, Mumbai.